

Inspection report: RA6604.214437.20

Client: JK Vloerverwarming
Fahrenheitstraat 39
NL-6716 BR EDE

Production plant: DE-40878 Ratingen

Third party control: 2nd half-year 2020

Production group: 1

Product: Floor heating pipes
Pipe PE-RT Type 0 Ø 14 x 2.0 mm

The exact material designation is available at SKZ - Testing GmbH.

Approval number: SKZ A 776

Letter of: ---

Reference: ---

Samples received: 2020-11-19

Sampling: ---

Test period: 2020-11-27 to 2020-11-27

Result: The requirements according to the HR 3.35:2011-04 specification for tests and inspection of SKZ - Testing GmbH are met.

The original language of the inspection report is German. In case of doubt, the German version is obligatory.

The inspection report comprises 2 pages.

Würzburg, 2020-11-30

Ap/wt

Ap

i. V.

Dipl.-Ing. Christian Winkler MBE
Deputy Group Manager
Inspection Body Plastic Pipe Center



i. A.

Dipl.-Ing. Frank Dorbath
Project Manager
Inspection Body Plastic Pipe Center

Die auszugsweise Wiedergabe, Vervielfältigung und Übersetzung dieses Berichtes bedarf der schriftlichen Genehmigung der SKZ - Testing GmbH. Die Ergebnisse beziehen sich auf die geprüften Produkte. Der Akkreditierungsumfang kann im Internet unter www.skz.de eingesehen werden.

1. Inspection scope

The inspection scope complies with the HR 3.35:2011-04 specification for tests and inspection of SKZ - Testing GmbH.

2. Sampling

Due to the travel restrictions because of the COVID-19 pandemic the samples could not be taken on site at the manufacturer's premises. The samples were selected by Mr. Ländner of SKZ - Testing GmbH on 4. November 2020 by remote audit and subsequently sent by the customer to SKZ - Testing GmbH. The sample material had been available at SKZ - Testing GmbH since 19 November 2020.

3. Results

3.1 Marking: 105 Meter JK JK FLEXTUBE inverse Soft 14x2 PE-RT/EVOH/PE-RT BRL 5602 PE-RT Type 0 zuurstofdicht volgens DIN 4726 / 16837 ISO 10508 class 4 6bar SKZ A776 KOMO K50264 XX.2232.040820 001 JK JK FLEXTUBE inverse Soft

3.2 Colour: natural-colored / adhesive agent green

3.3 Surface finish and condition as delivered: without objection

3.4 Dimensions

designation		actual value in mm		set value in mm	
		maximum	minimum	maximum	minimum
outside diameter	d ₁	14.2	14.2	14.3	14.0
wall thickness	s ₁	2.2	2.1	2.3	2.0
outside diameter basic pipe	d ₂	10.9	10.9	10.9	10.6
wall thickness basic pipe	s ₂	0.6	0.5	0.6	0.4

4. Assessment of production plant

The assessment of laboratory staff and device equipment as well as factory production control was carried out by Mr. Ländner of SKZ - Testing GmbH on 18 November 2020 within the scope of a document verification procedure.

Result: without objection

5. Complaints

According to the producer, during the inspection period there were no complaints about the products monitored.

